

Winston-Salem/Forsyth County Utilities

August 12, 2024 Update



Agenda




- 1 SE Forsyth County Sewer Expansion
- 2 Regulatory Update
- 3 Landfill Capacity Projections


SE Forsyth County Sewer Expansion

- Forsyth County received \$20M from the State budget to expand water and/or wastewater service in Southeastern Forsyth County.
- A site on Wallburg Road has been identified as the best location to use the available funding to build a new sanitary sewer lift station.
- A Request for Qualifications is currently advertised for Owner Advisor Services. Design-build project delivery will be used.









Regulatory Update - Water

- On April 10, 2024, EPA announced Maximum Contaminant Levels (MCLs) for six PFAS compounds
 - PFOA 4.0 parts per trillion
 - PFOS 4.0 parts per trillion
 - Health Hazard Index for HFPO-DA (Gen X), PFHxS, PFNA and PFBS
- Lead & Copper Rule Revisions & Improvements
 - Revises the regulatory timeline for service line replacement and new sampling requirements
 - Lead service line inventory is due by October 2024
- Microplastics
 - No current proposed regulations, only industry discussion




Regulatory Update - Wastewater

- Nutrient Management Plan for Yadkin River Basin
 - Phosphorus in first NPDES permit cycle and nitrogen in second following rule promulgation
 - Proposed regulations anticipated in early 2025 with final regulations in 2026
 - Timeline currently coinciding with needed capacity upgrades
- Capacity Upgrades for WWTPs
 - Based on recently completed collection system master plan, capacity upgrades will be required by 2035
- PFAS
 - Currently awaiting next steps from EPA and NC DEQ



Landfill Tonnage History & Projections

- Remaining life projected based on:
 - 3 year average tonnage, escalated by 0.9% (population growth rate)
 - In-place density of waste (measured annually)
 - Assumes C&D waste goes to Hanes after OSR LF closure in ~2030
- Increased tonnage in FY 2024
 - 250,031 tons vs. 238,866 in FY23
 - 3-year average decreased
- Hanes Landfill projected life extended
 - Projected to be at capacity in 2043





Hanes Landfill Construction Schedule



- MSE berm currently under contract
 - Construction time 12-18 months
 - Increases overall capacity by ~23%
 - Estimated to add ~7 years
- Remaining permitted horizontal expansion
 - Cells 6 & 7 (1-5 already constructed)
 - Partial construction of Cell 6 in FY26
 - Remaining cells and final portion of berm to be constructed by 2030





Winston-Salem/Forsyth County Utilities

Thank you

